

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. R. 3 W.	J-2
2. PROPERTY CONTROLLING IN SECTION <u>2*</u>	T. 27 N. R. 3 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION <u>11</u>	T. 27 N. R. 3 W. (XX = S89°38'40"E 165.34 & S00°46'30"W	9/K-4; K-4/14; XX (658.85 from 9)
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 28, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 8, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and subsequent restoration:~~

C. (continued)

K-4/14	XX
Set 5/8" Rerod w/Cap & cedar post	Set 5/8" Rod w/RLS Cap & red-top post
4" Spruce N51°E 20.45	Nail in 4" Cedar N57°W 13.28
3" Spruce N07°E 18.4	Nail in 5" W. Birch N12°W 9.15

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Set corner at calculated intersection of true 1/4 lines, per standard procedure for subdivision of sections. Concurs with previous survey of parcel in S 1/2 of NE 1/4, Sec. 2.
- 1 Set by standard survey procedure for subdivision of sections.
- K-4 Property corner set to delineate state park boundary.
- 4/14 Set by standard survey procedures for subdivision of sections. State park boundary corner.
- XX Property corner set to delineate state park boundary.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-2	1	9/K-4
Set 5/8" Rod w/RLS Cap	Set 5/8" Rod w/RLS Cap	Set 5/8" Rod w/RLS Cap
8" Twn.R. Pine S40°W 42.92	& Post	& red-top post
10" Maple S69°E 43.00	8" Twn. Maple S89°E 41.3	Nail in 3" Balsam S79°E 22.45
Cedar Post West 20'	12" Twn. Maple S48°W 28.2	Nail in 3" Spruce S28°E 16.92

SIGNED BY Kenneth Ostling DATE 1/15/80

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY

*As shown on map