

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27 N. R. 3 W.	E-10
2. PROPERTY CONTROLLING IN SECTION 29 _____	T. 27 N. R. 3 W.	14, 13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 26, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 14 Set by standard survey procedure for the subdivision of sections.
 - E-10 Fd. 1 1/4" pipe at road intersection, as established in previous local surveys.
 - 13 Set by standard survey procedure for the subdivision of sections. A 1/2" bar and 1 1/2" pipe is about 10' north and 2' west of proper location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>14 Set 5/8" x 30" iron bar w/cap 7" Cedar N19°W 63.8 ft. 5" Cedar S82°W 73.2 ft. N. End of bridge South 40.3'</p>	<p>E-10 Found 1 1/4" iron pipe 8" J. Pine S54°W 37.8 ft. 6" R. Pine N33°W 49.2 ft.</p>	<p>13 Set 5/8" x 30" iron bar w/cap 5" Cedar N36°W 13.7 ft. 10" Cedar N21°E 19.2 ft.</p>
--	--	--

SIGNED BY Kenneth Ostling DATE 8/20/81


SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY