LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Crawford
(County)

		Located In		Corner Code #
1. Public Land Survey	27N	T 3W	R	D-9
	27N	T 3W	R	E-10
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Section	S	T	R	
	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on September 27, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

D-9 G.L.O Addison P. Brewer 1859 Set quarter section post
Wit: W. Pine 13 N08°E 7 links
Tamarack 8 S64°W 3 links

E-10 G.L.O. Addison P. Brewer 1859 set quarter section post Wit: W. Pine 24 N22°E 7 links
W. Pine 22 N79°W 20 links

Liber 2 Page 111 Billy D. Buckler October 16, 1956 placed 1" pipe with 4" brass cap.
Wit: 14" R. Pine N03°E 47.5'
18" R. Pine S65°E 71.3'

Liber 2, Page 253 Kenneth Ostling May 1981 Found 1 ¼" pipe at road intersection as established in previous local surveys.
Wit: 8" J. Pine S54°W 37.8'
6" R. Pine N33°W 49.2'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

D-9 Found DNR monument

E-10 Found 1 ¼" iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Found DNR monument
Wit: 25" R. Pine S58°E 71.82'
15" R. Pine North 40.62'
13" R. Pine South 61.67'
8" W. Pine S53°W 48.51'
Blue Carsonite Post North 1'±

E10 Found 1 ¼" iron pipe
Wit: 11" R. Pine N31°W 49.33'
7" R. Pine S53°W 46.89'
5" W. Pine S71°E 38.07'
12" R. Pine N31°E 112.50'
Centerline of Wilcox Bridge road West 2'±

Signed by: Carl T. Kiiskila Date: 10-6-04

Surveyor's Michigan License No.: 33981

STATE OF MICHIGAN
CARL KIISKILA
LAND SURVEYOR
No. 33981
LICENSED LAND SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971
Revised May 14, 1975
Revised Jan. 1983
Revised Oct. 1995