

**SURVEY & REMONUMENTATION**

APR 07 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford

(County)

Located In:

**LIBER**

**3**

**PAGE 313**

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

5 JAN 98 10:37 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey

T28N R4W

T27N R4W

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

2. Property Controlling in Section

S\_\_\_

T\_\_\_ R\_\_\_

S\_\_\_

T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec.

S\_\_\_

T\_\_\_ R\_\_\_

S\_\_\_

T\_\_\_ R\_\_\_

J-13 X  
J-13

*[Handwritten signature]*

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James L. Schwandt, in a field survey on 10-13, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

J-13 T28N-R4W  
G.L.O. W. Warner, 1856  
8" Hemlock

G.D. Henning, 1976  
Fnd 1/2" Bar  
8" W. Pine N62°W, 43.0'  
10" N. Pine N9°30'E, 95.20'

N.F. Parker, 1983  
5/8" Bar, "R. Ostling, RLS"  
8" W. Pine N62°W, 49.0'  
10" Twin Pine N9 1/2°E, 55.20'

A. E. Newman, 1901  
Post  
40" W. Pine Stump N3 1/4°E, 40'

N.F. Parker, 1979  
1/2" Bar of Record  
8" W. Pine N62°W, 49.0'  
10" Twin Pine N9 1/2°E, 55.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. 1/2" Bar  
Fnd. Nail South side 14" W. Pine N62°W, 49.50'  
Fnd. Nail East side 12" Twin Pine N12°E, 55.45'  
Fnd. Nail Face 10" Maple N60°E, 14.10'  
Fnd. Nail West side 10" Poplar S25°E, 93.10'  
Fnd. Spk. 10" Maple N60°E, 14.30'

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
DATE OCT 16, 1997

*[Signature]*  
**Marvin E. Myers, P.S.**  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" iron with C.C.M.  
C.C.M. is accepted as a careful and faithful perpetuation to the position of the original corner.

Fnd. Nail South side 14" W. Pine N62°W, 49.50'  
Fnd. Nail East side 12" Twin Pine N12°E, 55.45'  
Fnd. Nail Face 10" Maple N60°E, 14.10'  
Fnd. Nail West side 10" Poplar S25°E, 93.10'  
Fnd. Spk. 10" Maple N60°E, 14.30'



Signed by James L. Schwandt  
Surveyor's Michigan License No. \_\_\_\_\_

Date 12-15-97