

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27. NR. 4 W.

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19, 20, 29, 30

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER -----

7" J. Pine - N74W - 47 $\frac{1}{2}$ links

7" J. Pine - N32E - 24 links

9" J. Pine - S15E - 24 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in Section 19. Corner was set by double proportionate measurement between our established section corner north, section corner west, 1/4 corner and river east, and original 1/4 corner south. No evidence of original B.T.s. A 3/4 iron rod is 83 links north and 7 links west of our corner, but has no supporting evidence and obviously was set without reference to other corners.

Corner was placed and witnessed May 24, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/26/57
REGISTERED LAND SURVEYOR