

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27. NR. 4 W.

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17,18,19,20 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

7" W. Birch - S42E - 66 links -----

9" W. Birch - N53E - 69 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of Section 19. Corner was set from probable original B.T., a large Cedar long butt which is down and rotted, but the only large Cedar at hand. Checks good with Manistee River east and an original 1/4 corner north.

Corner was placed and witnessed May 24, 1957

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE

7/20/57