

LAUSING

CRAWFORD

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> <del>XX</del> N. R. <u>4</u> <del>XX</del> W.	M-1 M-2 M-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 10-27- 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-1  
 15" Maple S45E 48.7'  
 15" Elm Stp.S 6W 72.8'  
 Houghton's NBTs in place

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 M-1 Found 1/2" re-rod and old spud bit verified by Houghton's N.B.T.s. Replaced with DNR Monument.

M-2 Set corner by proportionate measurement between Section corners.


M-3 Restored corner from USBT stumps, the SE in place with good marks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1	M-2	M-3
Set DNR Mon.	Set DNR Mon.	Set DNR Mon.
10" stem of tw Maple N55E 84.7'	11" W. Pine S53W 43.2'	8" W.Pine S70E 99.3'
8" Black Cherry S57W 32.55'	9" W. Pine S05E 74.1'	5" W.Pine N65E 42.0'
		P. Stp. N18W 21.5'
		18" Pine Stp S50E 41.2'

SIGNED BY Kenneth J. Ostling DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)