

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>27</u> ^{N.} <u>4</u> ^{W.}	<u>K-4; K-5; L-4; L-5</u>	
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} ^{S.} , R. _____ ^{E.} ^{W.}	_____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} ^{S.} , R. _____ ^{E.} ^{W.}	_____	
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 18, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-4 Found "T" iron set by Norton in previous survey in Sec. 11; best available evidence.
- K-5 Found 1 1/4" pipe as set by W. Wakenhut during survey in Sec. 11, at fence corner. Other surveys have used this as corner.
- L-4 Set by standard survey procedure for the subdivision of sections.
- L-5 Set by proportionate measurement between section corners. No evidence of a previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4	K-5	L-4
Set DNR mon. & red-top post	Set DNR mon. & red-top post	Set 1 1/4"x36" pipe & red-top post
6" W. Pine N38°E 61.0	6" R. Pine S16°E 43.7	8" Maple in clump of 4
6" R. Pine S05°E 59.4	6" W. Pine N67°E 30.6	N06°E 23.3
		5" Maple in clump of 3
		N72°W 15.0
L-5		
DNR monument and red-top post		
8" Beech S38°E 27.9		
9" Maple S40°W 19.5		

SIGNED BY Kenneth J. Ostling DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____