

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>6</u> , R. <u>4</u> E. <u>W.</u>	<u>1-4; 1-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>27</u> N. <u>S.</u> , R. <u>4</u> E. <u>W.</u>	<u>7; 13; 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. <u>S.</u> , R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Crawford

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 14 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- 1-4 Corner set by Henning Surveys from probable U.S.B.T. Used in subdivision of Sec. 10.
 - 1-5 This corner set from one possible U.S.B.T. and other pertinent measurement ties, to control subdivision of Sec. 10.
 - 7 Corner set by standard survey procedures.
 - 13 Set by standard survey procedure for the subdivision of sections.
 - 14 Set by standard survey procedure
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>1-4</p> <p>½" Re-rod in place</p> <p>14" R. Pine N80W 23.6'</p> <p>7" Balsam S38W 40.2'</p>	<p>7</p> <p>2½' of 1" Pipe</p> <p>6" R. Pine N12E 87.2'</p> <p>2" R. Pine S25E 28.3'</p>	<p>13</p> <p>2½' of 1" Pipe & Cedar Post</p> <p>7" Balsam N40E 4.7'</p> <p>12" Balsam S75E 29.6'</p>
<p>1-5</p> <p>Set 3' of 1" Pipe</p> <p>5" Cedar N79E 8.0'</p> <p>4" Cedar S21W 2.2'</p>	<p>14</p> <p>2½' of 1" Pipe</p> <p>6" Cedar N31W 49.2'</p> <p>8" Tw. Cedar S89W 30.2'</p>	

SIGNED BY Kenneth J. Ostling DATE 4/12/74

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

Crawford