

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

10 FEB 95 8:36 A.M.

ELIZABETH H. WIELAND
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

CRAWFORD COUNTY
PEER GROUP APPROVAL
Date DEC 22, 1994

LIBER

3 PAGE 178

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

ALSO ACT 345, PA 1990

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Cor. Set by James Mullet 1839. ½" Bar & Cap (Illigible)
 No record found Resurveyed 1858 by Walter Warner D.S. Cor. found. Unknown origin
 1. Pine 12 N83°E, 07'.
 2. Pine 12 N37°W, 05'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Bar with illigible cap. Origin Unknown. No other evidence found.
 G.L.O. dist. to C-1 in T28N-R1W - 3614.82' Meas. 3612.99'.
 G.L.O. dist. to K-1 in T28N-R2W - 5280' Meas. 5253.15'.
 G.L.O. dist to A-2 2620.20' (Warner) Meas. 2635.52'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Crawford Co. Mon. Set at exact location of ½" Bar.
 1. Set Spk. 8" Pine N37°E, 91.79'.
 2. Set Spk. P.P. N53°E, 43.71'.
 3. Set Spk. 8" Oak S38°W, 86.69'.
 4. Set Spk. 6" Cherry N24°W, 117.72'.
 This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss
 Surveyor's Michigan License No. 20703

Date January 3, 1995

