

**SURVEY &
REMONUMENTATION**

APR 27 1995

COMMISSION

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

10 FEB 95 8:37 A.M.

ELIZABETH H. WIELAND
REGISTER OF DEEDS

CRAWFORD COUNTY
PEER GROUP APPROVAL

Date Dec 22, 1994

Marvin E. Myers
Marvin E. Myers, P.S.

LIBER

3 PAGE 179

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ALSO ACT 345, PA 1990

For corners in

<u>CRAWFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Wayne E. Boss, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner set by James Mullet 1839. No record fd. Resurveyed 1858 by Walter Warner D.S. set qr. Sec. Post.
1. Tamarack 7 S35°N, 8 lks.
2. Tamarack 7 N57°W, 28 lks.

Set 1/2" Bar & Cap by single proportionate meas. between A-1 and A-3. No cor. evidence found. Set Witnesses (see Sec. C)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner evidence found, set 1/2" Ir. & Cap by single proportionate measure on line between A-1 and A-3.

G.L.O. dist. to A-1 2620.2' Meas. 2625.60'.
G.L.O. dist. to A-3 2640.0' Meas. 2645.44'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 Crawford Co. Mon. Set at exact location of 1/2" Ir.
1. Set Spk. 16" Poplar N84°E, 89.26'.
2. Set Spk. P.P. S53°E, 77.30'.
3. Set Spk. 14" Poplar S57°W, 34.72'.
4. Set Spk. 14" Pine N52°W, 50.72'.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Wayne E. Boss PS
Surveyor's Michigan License No. 20703

Date January 3, 1995

