

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

CRAWFORD COUNTY
 PEER GROUP APPROVAL
 Date Dec 29, 1994
Wayne E. Boss
 Marvin E. Myers, P.S.

LIBER 3 PAGE 183

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO ACT 345, PA 1990

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED

10 FEB 95 8:37 A.M.

ELIZABETH H. WIELAND
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1839 by James Mullet
 set quarter Section Post.
 1. Pine 8" S08°W, 20 lks.
 2. Pine 4" N26°W, 10 lks.

1/2" Bar Set-Origin Unknown used and witnessed
 by Norman Parker in subsequent surveys. L 214, pg. 386. L 319, pg.361
 1. BT 22" N. Pine N28°W, 19.8'.
 2. BT 22" N. Pine S53°W, 67.7'.
 3. Con. Mon. S09°E, 31.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" Iron Bar 170' West of two-track trail. Cor. previously witnessed by Norman Parker.

- Fd. Spk. in 18" Pine N30°W, 20.42' (Parker N28°W, 19.8')
 - Fd. Spk. in 8" Oak N09°E, 10.15'.
 - Fd. DNR Mon. S10°E, 37.45' (Parker S09°E, 31.8')
 - Fd. Blaze 18" Pine S50°W, 67.6'.
- G.L.O. to A-5 2640' Meas. 2536.08' (N. Parker).
 G.L.O. to A-7 2640' Meas. 2596.80' (N. Parker).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6 Set Crawford Co. Mon. at exact location of 1/2" Ir. Bar.
- Spk. in 18" Pine N30°W, 20.42'.
 - Spk. in 8" Oak N09°E, 10.15'.
 - DNR Mon. S10°E, 37.45'.
 - Spk. Set in blaze 18" Pine S50°W, 67.92'.

This position not established by government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss
 Surveyor's Michigan License No. 20703

Date Jan 3, 1995

