

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
Date DEC 22, 1994
Marvin E. Myers
Marvin E. Myers, P.S.

LIBER 3 PAGE 184

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

10 FEB 95 8:38 A.M.

ELIZABETH H. WIELAND
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Wayne E. Boss, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James Mullet 1839
Set Post cor. Sections 13 & 24
1. Pine 8" N79°W, 41 lks.
2. B. Oak 9" S71°W, 19 lks.
Mullet meas. 80.0' chains from
M-9 W. Warner D.S. Measured
83.25' chains in 1858.

3/4" Iron Pipe Set. Unknown origin
N. Parker used in 1973 survey and
subsequent surveys. L 130, pg. 537. L 319, pg. 361.
Unrecorded Parker Wlt. Fd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" Pipe.

- 1. Fd. tag #16939 on P.P. S49°W, 18.62'.
 - 2. Fd. 3/4" Pipe West 29.98'.
- G.L.O. Dist. to A-6 Mullet 1839 - 2640 Meas. 2596.80' (N. Parker).
G.L.O. Dist. to A-8 Mullet 1839 - 2640 Warner 1858 - 2871 Meas. 2852.30' (N. Parker)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-7 Crawford Co. Mon. Set at exact location of 3/4" Pipe.
- 1. Tag on P.P. S49°W, 18.62'.
- 2. 3/4" Pipe West 29.98'
- 3. Spk. 20" Oak N75°E, 59.28'.
- 4. Spk. 18" Oak S20°E, 38.36'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss
Surveyor's Michigan License No. 20703

Date January 3, 1995

