

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
Date Dec 22, 1994  
Wayne E. Boss  
Marvin E. Myers, P.S.

LIBER 3 PAGE 188

CRAWFORD COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO ACT 345, PA 1990

For corners in

CRAWFORD (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

10 FEB 95 8:38 A.M.

ELIZABETH H. WIELAND  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James Mullet 1839 Set Post Cor.  
Sections 25 & 36.  
1. Pine 22" S52°W, 52 lks.  
2. B. Oak 8" N44°W, 12 lks.

1/2" Bar set by N. Parker 1979, L. 180, pg. 640  
1. 10" Oak N84°W, 12.1'.  
2. 4" N. Pine S15°E, 25.6"  
No Cor. Cert. filed. Apparently re-wit. by Fred King in 1991.  
in Survey L. 331, pg. 107.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" Bar & Cap #16939

1. Fd. Blz. & Spk. 6" Oak N30°E, 14.48'.
2. Fd. Blz. & Spk. 6" Oak East 30.77'.
3. Fd. Blz. & Spk. 6" Pine S21°W, 26.44'.
4. Fd. Blz. & Spk. 12" Oak West 12.32'.

Cor. is at End of Single Strand Fence.

G.L.O. Mullet 1839 - 2640 to A-10 W. Warner D.S. 1858 2642.64' Meas. 2667.70' (N. Parker)

G.L.O. Mullet 1839 - 2640 to A-12 Meas. 2637.94' (F. King)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Set Crawford Co. Mon. at exact location of 1/2" Bar.

1. Spk. 6" Oak N30°E, 14.48'.
2. Spk. 6" Oak East 30.77'.
3. Spk. 6" Pine S21°W, 26.44'.
4. Spk. 12" Oak West 12.32'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss  
Surveyor's Michigan License No. 20703

Date January 3, 1995

