

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MAR 29 2000

Crawford SECTION
(County)

Located In: Corner Code #

- 1. Public Land Survey T 28N R 1W B-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

22 FEB 2000 12:45 PM

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ LIBER 4 PAGE 83

I, Ronald C. Brand, in a field survey on October 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 North One-Quarter corner of Section 6

1839 James Mullett West on North side Section 6 at 40.00 chains set 1/4 Section post, Aspen 10" N82°W 17 links, Cherry 10" N71°E 11 links

1856 Resurvey Harvey Mellon West on North side Section 6 at 40.00 chains set 1/4 Section post Y. Pine 18" N48°E 11 links, Spr.Pine 10" N8°W 39 links

1968 DNR Retracement Kenneth Ostling, set DNR monument by single proportionate measure

1968 S.O. Thorsen County Surveyor Liber 3, Page 498, Fd. Conservation Dept. standard monument Oak 9" N87°E 29.3', Oak 18" S10°E 61.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 North One-Quarter corner of Section 6

Fd. Standard DNR monument 62.5' South of centerline trail road Fd. cedar post scribed W 1/4 next to Mon.
Fd. Oak 11" N85°E 29.60' Fd. Oak 20" S12°E 61.97' w/toe blaze

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 North One-Quarter corner of Section 6

Fd. Standard DNR monument is accepted as a careful and faithful reestablishment of the position of the original corner. Monument is 62.5' South of centerline trail road.

Set Nail & Tag 11" Oak N85°E 29.60' Set Nail & Tag 20" Oak S12°E 61.97'
Set Nail & Tag 5" Poplar N07°W 28.41' Set Nail & Tag N72°W 24.19'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 19, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Date 12/22/99

Signed by _____
Surveyor's Michigan License No. 43046

