

DEC 3 1999

LIBER 3 PAGE 342

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Crawford (County), Located In: T 28NR 1W, Corner Code # C-10, and numbered sections 1-5 for survey details.

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 DEC 98 9:48 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on Nov 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numerical data points for survey locations.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1858 W. Warner, DS James H. Mullet D.S. Mon: Post Wit: 12" W. Pine N17°E 25 links 12" W. Pine S72°E 17 links L. 182, P. 295 Sept 27, 1979 Norman F. Parker, P.S. 16939 Mon - 5/8" Bar Wit: NBT 8" Maple S43°E 11.0 (Henning) NBT 6" Maple S41°W 36.2 (Henning) NBT 8" Maple N13°W 33.5

Farnham, Wirres & Berning Mon - not given (Pipe typ.) Wit: Oct 6, 1990 Marvin E. Myers, P.S. 31600 Mon - Found 1/2 bar of record.

LCRC L. 2, P. 181 Jun 16, 1978 N. Parker, P.S. #16939

Mon - Found 5/8 " bar and old witness Trees with G.D. Henning Tags Wit: NBT 8" Maple S43°E 11.0 (Henning) NBT 6" Maple S41°W 36.2 (Henning) NBT 8" Maple N13°W 33.5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Mon - Found 5/8"x28" bar; found dead 8" maple lying on the ground with GDH nail & tag facing up. Set nail in the base of Henning stump of this twin maple; blazed dying 6" maple with G.D. Henning nail & tag S41°W 36.2; found 8" Maple N13°W 33.5; found 3" Cedar Post East 0.90; found GLO Stump hole N17°E (25 links) 16.5. Accepted as a perpetuation of the Original Government Corner. Replaced 5/8" bar with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Mon - Standard Crawford County Monument.

Wit:: Set nail & tag in W. side 5" Maple S41°E 11.96 Set nail & tag in S. side 5" Maple in clump S71°W 17.67 Set nail & tag in E. side 10" Maple N13°W 33.90 Set nail & tag in N. side 8" Poplar N73°E 15.31 Set Carsonite Post North 2.0±

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 4, 1998

Signature of Marvin E. Myers, P.S.
Marvin E. Myers, P.S.
County Surveyor

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 22, 1998

