

SEP 22 1999

LIBER 3 PAGE 341  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

29 DEC 98 9:48 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on Dec 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3		2	1	
3														
4	7						8			9		10	11	12
5														
6	18			17			16			15		14		13
7														
8	19			20			21			22		23		24
9														
10	30			25			28			27		26		25
11														
12	31			32			33			34		35		36
13														

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO - 1858 W. Warner, D.S. Mon - Post Wit: 5" S. Pine N71°W 17 lks. 5" S. Pine S42°E 5 lks.	L163, P. 110 Sept 1977 N. Parker ,PS Mon - 1/2" bar & cap # 16939 Wit: Face of P. Pole N78°W 64.0 6" J. Pine S23°E 27.0 8" J. Pine N55°E 26.2 Cen. of Lovells Rd is 32.61 West
--	---

Farnham, Wirries, & Berning  
Mon - not given  
Wit: none given

L. 247 P. 45 May 28, 1986 F. J. King #25852 Mon - Fd. 1/2" re-rod Wit: Center of Road West 32.6±
--

LCRC L. 2, P. 151 Sep 1977  
N. Parker # 16939  
Mon - Set 1/2" bar & cap midway & on line between section Cor. (s) by farnham, moores & wirries civil Engineers & surveyors - Toledo, Oh.  
Wit: Face of P. Pole N78°W 64.0  
6" J. Pine S23°E 27.0  
8" J. Pine N55°E 26.2  
Cen. of Lovells Rd is 23.75 west

L.463, P. 423 Aug 14, 1998 R. Brand #43046  
Mon - FD. Bar & Cap #25852 as rec. in L2, P151  
Wit: 24.3 East & 18 South of Intersection of Rd.  
Face of P. Pole S72°W56.2  
Set spike in 10" J. Pine S51°E 57.65  
Set spike in 12" J. Pine N88°E 119.55  
Set spike in 5" J. Pine N80°W 84.64  
(Note: Witness matches E-11 L.463, P.423)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" bar & cap #16939; found Face of P. Pole N78°W 64.0; found 6" J. Pine S23°E 27.0; found 8" J. Pine N55°E 26.2; found Center of Road West 32.6±; found nail in 6" J. Pine S34°E 26.88, found nail 8" J. Pine N53°E 26.60; found PK nail in P. Pole S31°W 132.60; found PK nail in P. Pole N31°W 128.80. Accepted 1/2" bar as the best available evidence of the position of the Original Corner. Replaced with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument  
Wit: Set Carsonite Post East 2'±  
Found Spike in P. Pole S31°W 132.60'  
Found spike in P. Pole N31°W 128.88'  
Found 6" J. Pine S23°E 27.0  
Found nail 8" J. Pine N53°E 26.60

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 4, 1998

*Marvin E. Myers*

Marvin E. Myers, P.S.  
County Surveyor

Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date Dec 2, 1998