

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

| | | |
|------------------------------------|---|--------------------------------------|
| <u>Crawford</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>27NR 1W</u> T <u>28N R 1W</u> T ___ R ___ T ___ R ___ | G-13 <u>G-1</u> _____ _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ S ___ T ___ R ___ | _____ _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ S ___ T ___ R ___ | _____ _____ |

[Signature]
STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
19 DEC 97 2:36 P.M.
SANDRA MOORE
REGISTERED PROFESSIONAL SURVEYOR
File Number

4. Lot No. _____, Recorded Plat **LIBER 3**
5. Private Claims _____

PAGE 303

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Marvin E. Myers, in a field survey on May 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. 1839
James H. Mullet D.S.
Mon: Post
Wit: 22" Y. Pine N21°E 23 links
10" Aspen N61W 82 links
 - GLO - 1858 W. Warner, D.S.
Mon - Post
Wit: 20 Y. Pine S20°E 30 lks.
18" Y. Pine S80°W 50 lks.
 - 1933 F. N. Smith for G.F. Delamater
Mon - unknown
Wit: 20" Y. Pine S44°E 94
 - Oct 6, 1989 Don Marlatt, P.S.
Mon - Reset from DNR Witness
Wit: Found 9" J. Pine N07°W 30 lks
Found 9" J. Pine S50°W 56 lks.
10" J. Pine S56°W 16.81 feet
10" J. Pine N65°W 26.96 feet
 - Carlos LaGarica, Ausable State Forest
Mon: Found Corner set 18" Monument
Wit: Found SW & SE Stumps good and in place, NE stump good, NW hole, ran S01°42'W found line tree stump at 3.13 chains; found swamp 4 chains East; Highway is 1.20 chains North. Set Pits N45°E 0.50 chains & S45°W 0.50 chains.
 - July 3, 1953 Dept. of Conservation
Mon - 1" Pipe with brass cap, previously perpetuated by Marcus Schaaf
Wit: Found three original "BT'S" in poor condition.
9" J. Pine N7°W 30 lks.
9" J. Pine S50°W 56 lks
 - L. 417, P. 606 F. King, P.S. Aug 13, 1996
Mon - Found 1/2" iron in centerline of E-W Road and on line with fence N-S
Wit: 12" J. Pine N45°E 58.22
6" J. Pine S30°E 38.58
6" J. Pine S30°W 40.22
15" J. Pine N40°W 66.20

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE June 9, 1997
[Signature]
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing the corner:

Found 1/2" bar over top of 60d spike with flagging in centerline of E-W Road on line with fence N-S; found all accessories recorded in L. 417, P. 606. **This position was not accepted.**
Found 1/2" iron; found three GLO BT's did not find the 10" Aspen; found Pits N45°E 0.50 chains & S45°W 0.50 chains; found 9" J. Pine N7°W 30 lks; found 9" J. Pine S50°W 56 lks; found 20" Y. Pine (stump) S44°E 94; found 10" J. Pine S56°W 16.81 feet and 10" J. Pine N65°W 26.96 feet. Replace in exact location with a Standard Crawford County Monument.
Accepted this position as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
Wit: Found 9" J. Pine N07°W 30 lks
Found 9" J. Pine S50°W 56 lks.
10" J. Pine S56°W 16.81 feet
10" J. Pine N65°W 26.96 feet
Set Carsonite Post North 2'
Found 1/2" bar N63°02'18"W 192.55 in centerline of road on N-S fence line.

Signed by *[Signature]*
Surveyor's Michigan License No. 31600

Date Dec 15, 1997

