SURVEY &
RIEN... ...MENTATION

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Also Act 345, PA 1990

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 DEC 99 3:01 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Crawford (County) Located In: Corner Code #

1. Public Land Survey		T 28N	R 1W	L-13
		T 27N	R 1W	L-1
		T____	R____	
		T____	R____	
2. Property Controlling	S____	T____	R____	
in Section	S____	T____	R____	
3. Miscellaneous	S____	T____	R____	
Property in Sec.	S____	T____	R____	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



LIBER 4 PAGE 66

I, James L. Schwandt, in a field survey on May 14, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1.) Post set by James Mullett, D.S., 1839
Pine 3", N70°E, 44 links
Pine 3", N45°W, 12 links

2.) Carlos Laguire (date unknown)
Visited corner

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Jan 7, 1999
Marvin E. Myers MEM
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe with Department of Conservation brass cap, 1.5' North of a red topped post
No witnesses found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1 1/2" pipe with Department of Conservation brass cap, 1.5' North if a red topped post and is accepted as a careful and faithful reestablishment of the position of the original corner.
Spike in 12" Pine, S11°W, 126.55'
Spike in 14" Pine, S44°W, 146.14'
Spike in 10" Pine, N70°E, 101.80'
Spike in 8" Pine, N6°E, 157.02'

STATE OF MICHIGAN
JAMES L. SCHWANDT
PROFESSIONAL SURVEYOR
No. 26466
LICENSED PROFESSIONAL SURVEYOR

Signed by James L Schwandt Date 12-10-99
Surveyor's Michigan License No. 26466

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28,
REVISED MAY 14,
REVISED JAN.,
REVISED OCT.,