

CRAWFORD COUNTY REMONUMENTATION
LIBER 3 PAGE 112
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED FOR RECORD THIS
6th DAY OF Dec, 1993
3:20 am/pm, IN LIBER 3 1/2
PAGE 112
Elizabeth A. Williams
Register of Deeds
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on October 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley Mon. - Post WIT: 7" B.Oak N13°W 50 lks. 9" B.Oak S61½°E 64 lks.	L.249,pg.163 P.S. 18654 Mon. - 1" Bar WIT: 20" N.Pine S65°E 105.60' 12" J.Pine N45°E 118.30' 24" Pine Stump N11°E 134.00'
June 1921 Pg. 155 County Surveyor Mon. - Conc. Post Set	Consumers Power Co. Oct. 1967 Mon. - Fd. 3/8" Pin Blaze & Tag 12" Norway SE 105.55' Blaze & Tag 12" Oak NW 103.58' Cement Marker SW 57.33'
Norman Caldwell 1968 Mon. - Fd. ½" Bar WIT: 10" N.Pine S65°E 105.60' 24" Pine Stump S10°E 134.00' 8" J.Pine N45°E 118.30'	Consumers Power Co. Mar. 1967 Mon. - Fd. ½" Bar WIT: 10" N.Pine S65°E 105.60' 8" J.Pine N45°E 118.30' 24" Pine Stump S10°E 134.00' Concrete Post SW 57.30'

Consumers Power Co. Mar. 1967 Mon. - Fd. ½" Bar WIT: 10" N.Pine S65°E 105.60' 8" J.Pine N45°E 118.30' 24" Pine Stump S10°E 134.00' Concrete Post SW 57.30'	1926 G.Delamater Mon. - Fd. Cedar Post & older Post WIT: 8" B.Oak N69°W 35.50' 24" Y.Pine S10°E 134.00'
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Bar and Cap in mon. box in centerline of road N-S & E-W with Montmorency County Remonumentation Cap on same Mark P.S. 18654. Verified location by measurement to accessories of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Fd. Std Montmorency Mon. in pav't box
WIT: US Army BM Mon. with brass cap S64°E 122.05'
15" Norway S57°E 105.38'
3" Norway S23°W 119.25'
8" Norway N36°W 119.35'



Signed by Marvin E. Myers Date Dec 6, 1993

Surveyor's Michigan License No. 31600

DATE DEC 6, 1993 PEER GROUP APPROVAL