

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THE
6th DAY OF Dec, 1993
3:20 am/pm, IN LIBER 34
PAGE 11
Elizabeth H. Williams
Register of Deeds
Register of Deeds Stamp & File Number

For corners in
Crawford _____
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T 28N R 1W	M-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Marvin E. Myers, in a field survey on Nov 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley Walker 1992
Mon. - Post Mon. Not set
WIT: 8" B.Oak N44 3/4°W 62 lks.
Consumers Power company Oct 1967 H.W. Darcey and Norman Caldwell
Mon- Not Set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Reestablished corner position at single proportionate between standard corners and accepted as a careful and faithful establishment of the position of the corner. Two pipes in the vicinity were found and not accepted. The location of pipes are noted below as accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- STD. 2"x21" Crawford County Monument
Wit- 2" pipe South 40.5±
1 1/2" pipe South 3.3±
Crawford County nail & tag in N. face 20" Oak N85°W 46.52
Crawford County nail & tag in E. face Oak N8°W 74.22
Crawford County nail & tag in N. face 5" J. Pine East 60.77
Crawford County nail & tag in NE face 6" R. Pine S25°E 87.07

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *Marvin E. Myers* Date Dec 6, 1993
Surveyor's Michigan License No. 31600
DATE DEC 6, 1993 PEER GROUP APPROVAL

2847