

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF Dec, 1993 AT
3:20 am/pm, IN LIBER 34
PAGE 109.

Elizabeth H. Wiseman
Register of Deeds
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on OCT 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley
Mon. - 14" Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pipe set in concrete base. This type of monument is typical of the type of monuments used by Marcus Schaaf (1911-1941) State of Michigan Forestry Dept. Surveyor. No record of Schaaf setting this corner was found. Telephone conversation with Carl Roser, P.S. DNR confirmed that the monument could be by Schaaf and that some of Schaaf records are gone. The monumented location was accepted as the best available evidence of the position of the corner replaced with standard Crawford County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Set Std. 22" Crawford County Mon.
WIT: nail & tag NW 9" J.Pine N42°E 23.22'
nail & tag N 26" R.Pine S86½°E 42.37'
nail & tag NW 10" J.Pine S25°W 16.30'
nail & tag NE 9" Oak N42°W 30.35'



Signed by Marvin E. Myers Date Dec 4, 1993
Surveyor's Michigan License No. 31600
DATE NOV 29, 1993 PEER GROUP APPROVAL