

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 28N R 1W	M-6
	T R	_____
	T R	_____
	T R	_____
2. Property Controlling in Section	S T R	_____
	S T R	_____
3. Miscellaneous Property in Sec.	S T R	_____
	S T R	_____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
6th DAY OF Dec, 19⁹³
2:20 am/pm, IN LIBER 3 1/2
PAGE 107

Elizabeth D. Wiseman
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on NOV 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley	DNR 1979 P.S. 10068
Mon. - Set Post	Mon. - DNR Mon.
WIT: 7" B.Oak N82 1/2°W 36 lks.	WIT: 5" W.Oak N50°E 17.46'
	4" R.Oak N54°W 43.86'
	W 1/2 Sec. 18, T28N, R1E South 69.70'
	Walker Survey Feb. 1992
	Mon. - DNR Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Std. DNR Monument verified location by measurement to accessories and corners of record. And is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left Std. DNR brass capped monument in place
WIT: nail & tag NW 8" W.Oak N52°E 17.80'
nail & tag NE 3" Poplar S59°E 7.37'
nail & tag N 4" R.Pine N85°W 21.25'
nail & tag E 6" J.Pine N26°W 30.50'



Signed by Marvin E. Myers Date Dec 4, 1993
Surveyor's Michigan License No. 31600
DATE NOV 29, 1993 PEER GROUP APPROVAL