

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

| | | |
|---------------------------------------|-------------------------|-----------------|
| Crawford (County) | Located In: | Corner Code --# |
| 1. Public Land Survey | T 28N R 1W | M-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED FOR RECORD THE
6th DAY OF Dec, 1993
3:20 am/PM IN LIBER 34
PAGE 106
Elizabeth H. Wicks
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on NOV 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|--|--|
| GLO - May 1839 Hodgeson & Sibley Mon. - Post WIT: 14" Pine S46°W 24 lks. 12" Pine N42°W 12 lks. | DNR - 1979 P.S. 10068 Mon. - DNR Mon. 20" R.Pine S35°E 89.10' SW Sec. 18, T28N, R1E South 58.50' Walker Surveys Feb. 1992 Mon. - DNR Mon. |
| DNR - Schaaf Set Mon. from original WIT: 20" R.Pine S35°E 135 lks. | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument noted above accepted as a perpetuation of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. DNR Monument
WIT: nail & tag S. face 6" W.Pine N83°E 11.57'
nail & tag W. face 7" W.Pine S15°E 14.20'
nail & tag N. face 8" Balsam S70°W 14.90'
nail & tag E. face 4" W.Pine N14°W 10.77'



Signed by Marvin E. Myers Date DEC 4, 1993
Surveyor's Michigan License No. 31600
DATE NOV 29, 1993 PEER GROUP APPROVAL