

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

Crawford (County)	Located In:	Corner Code --#
1. Public Land Survey	T 28N R 1W	M-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED FOR RECORD THIS
6th DAY OF Dec., 1993
3:20 am/pm IN LIBER 3 4c
PAGE 104

Elizabeth H. Williams
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Nov 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley DNR - Schaaf
Mon. - Post Mon. -
WIT: 14" Pine S06°W 17 lks. WIT: 10" J.Pine N28°W 32 lks.
17" Pine NW 70 lks. 10" J.Pine S50°W 62 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Pipe (typical Schaaf monument) with Dept. of Conservation Pipe and Plate inside. Verified position by measurement to accessories and corners of record; and is accepted as the best available evidence of the position of the original corner. Replaced monuemnt with Std. 22" Crawford County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Std. 22" Crawford County Mon.
WIT: nail & tag N. side 4" Cherry S45°W 32.74'
nail & tag NE 3" Maple N35°W 12.63'
nail & tag NE 4" Oak S69°E 42.20'
nail & tag W. 5" Cherry S35°E 32.90'



Signed by Marvin E. Myers Date DEC 4, 1993

Surveyor's Michigan License No. 31600

DATE NOV 29, 1993 PEER GROUP APPROVAL

2047