

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 1W	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

FILED FOR RECORD THIS
6th DAY OF Dec, 1993
3:20 am/PM IN LIBER 34
PAGE 107
Elizabeth A. Wicklund
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on NOV 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley	Schaaf	DNR July 1970 K.Ostling
Mon. - Post	Mon. - Fd. by crew	Mon. - Std. Dept. Mon.
WIT: 30" Pine N07°W 1.20 chains	WIT: One original BT in place. Poor condition NBT 9" Tamarack West 43 lks.	WIT: none given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Dept. of Conservation Monument verified position by measurement to accessories and corners of record and accepted as a perpetuation of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Dept. of Conservation Mon.
WIT: nail & tag in E. 5" Cherry N25°W 17.54'
nail & tag in SE 4" Cherry N19½°E 17.83'
nail & tag in S. 5" Poplar N60½°E 31.88'
nail & tag in N. 3" Poplar S72°E 62.78'
waters edge of creek is 8' South



Signed by Marvin E. Myers Date DEC 4, 1993

Surveyor's Michigan License No. 31600

2847