

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS
6th DAY OF Dec, 1993 AT
8:20 am/pm IN LIBER 3 4c
 PAGE 102
Elisha H. Wieland
 Register of Deeds
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Marvin E. Myers, in a field survey on November 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - May 1839 Hodgeson & Sibley	DNR 1953 Schaaf
Mon. - Post	Mon. -
WIT: 8" Pine S12°W 7 lks.	WIT: 6" J.Pine S65°E 33 lks.
16" Pine N74°W 12 lks.	10" J.Pine S45°W 39 lks.

DNR July 1970 K.Ostling
 Mon. - Std. Dept. Mon.
 WIT: none given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Monument. Verified position by measurement to accessories and corners of record and accepted as the best available evidence of the re-establishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservations Dept. Monument
 WIT: nail & tag SE 10" J.Pine N32°E 21.74'
 nail & tag NE 11" J.Pine N42°W 46.10'
 nail & tag S. 7" J.Pine S78°W 23.80'
 nail & tag NE 9" J.Pine S34°E 59.90'



Signed by Marvin E. Myers Date Dec 7, 1993

Surveyor's Michigan License No. 31600

DATE NOV 29, 1993 PEER GROUP APPROVAL

2847