

**LIBER 3 PAGE 101**  
CRAWFORD COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF CRAWFORD

For corners in

<u>Crawford</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS  
6<sup>th</sup> DAY OF Dec, 1993 AT  
3:20 am/pm, IN LIBER 3 4c  
 PAGE 101.

*Elizabeth H. Wieland*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on NOV 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO - May 1839 Hodgeson & Sibley	DNR - July 1970
Mon. - Post	Mon. - Std. Dept. Mon.
WIT: 10" Pine S53°W 18 lks.	WIT: none given
8" Pine N48°W 31 lks.	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Dept. of Conservation Monument verified position by measurement to accessories and corners of record and accepted as the best available evidence of the re-establishment of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon. - Left in place Std. Dept. of Conservation Mon.  
 WIT: nail & tag NE 6" J.Pine N52°W 38.48'  
 nail & tag NW 11" J.Pine S46°W 54.43'  
 nail & tag N. 12" Oak S57°E 28.30'  
 nail & tag E. 11" Oak N16°E 57.35'



Signed by Marvin E. Myers Date DEC 4, 1993

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

DATE NOV 29, 1993 PEER GROUP APPROVAL

2847