

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 1 W.

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 11 & 14

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER

6" J. Pine - N 68 P - 40 Links

10" J. Pine - S 50 W - 43 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew, while making a partial resurvey of this Township. In the absence of any original evidence, the corner was placed in line, and at a proportionate distance between the Section Corners.

Corner was placed and witnessed August 18, 1953.

SURVEYORS SEAL

SIGNED Dean C. DeLoe DATE 2/18/54
REGISTERED LAND SURVEYOR