

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 1 W.

Crawford COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 14, 15, 22, 23

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER

10" J. Pipe - S 20 W - 22 Links

8" J. Pipe - S 75 E - 25 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Burned over land, no original evidence at corner.

Corner was placed and witnessed June 9, 1953.

SURVEYORS SEAL

SIGNED Dean C. DeLoe DATE 2/9/54
REGISTERED LAND SURVEYOR