

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 NR. 1 W.

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 1 & 12 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER -----

10" Cedar - S 35 W - 5 Links -----

10" Cedar - N 20 E - 11 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew, while making a partial resurvey of this Township. In the absence of any original evidence, the corner was placed in line, and at a proportionate distance between Section Corners.

Corner was placed and witnessed June 8, 1953.

SURVEYORS SEAL

SIGNED John C. Anderson DATE 2/8/54
REGISTERED LAND SURVEYOR