

Kennedy

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 28 N. R. 1 W.	I-6; M-5; M-6; (M-7)
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 23, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A = Description of original monument and accessories and/or subsequent restoration:~~

C. (continued) M-7
 Left DNR Monument in Place
 *20" R. Pine S35°E 89.1
 *1953 NBT
 SW Sec. 18 T28N-R1E
 South 58.5

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-6 Set corner by proportionate measurement between section corners.
- M-5 Found concrete tile mon. at corner, located and used in previous survey by this Department in 1953.
- M-6 Set corner midpoint, on line, between section corners. Previous Schaaf mon. removed in logging activity. Corner first located in 1953 survey by this Department.
- M-7 Corner originally restored by M. Schaaf, replaced with DNR mon. in 1953 survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6	M-5	M-6
Set DNR Mon. & Cedar Post	Set DNR Mon. & Cedar Post	Set DNR Mon. & Cedar Post
4" W. Oak N20°E 3.5	4" J. Pine S58°W 16.41	5" W. Oak N50°E 17.46
6" J. Pine S55°W 11.55	4" J. Pine (Old NBT)	4" R. Oak N54°W 43.86
	N68°W 16.46	W¼ Sec. 18 T28N-R1E
	NW corner Sec. 18 T28N-R1E	South 69.7
	South 81.0	

SIGNED BY Kenneth J. Ostling

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CRAWFORD COUNTY

