

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 28 N. R. 1 W.	(K-5); L-5; L-6; (L-7)
2. PROPERTY CONTROLLING IN SECTION.	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 23, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 C. (continued)

L-7  
 DNR Monument & Cedar Post  
 8" Poplar S44°E 8.82  
 4" Maple S62°E 35.55


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 K-5 Corner previously set in 1953 retracement in this area. Originally established by double proportionate measurement. No previous corner.  
 L-5 Set corner by proportionate measurement between section corners. Can locate no previous corner.  
 L-6 Set corner at calculated intersection of true 1/4 lines, per standard survey procedure.  
 L-7 Reset 1/4 corner to midpoint, on line, between section corners, slightly north of 1953 position. No previous corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5	L-5	L-6
Left 1953 DNR Monument in Place	Set DNR Mon. & Cedar Post	Set 5/8" Rod w/RLS Cap and Cedar Post
*9" J. Pine S40°E 19.8	6" J. Pine S20°W 24.22	14" Cedar S73°E 13.68
*8" J. Pine N55°E 21.8	7" J. Pine N55°W 31.54	12" Cedar S25°E 24.05
*1953 NBT's		

SIGNED BY Kenneth J. Ostling DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CRAWFORD COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET