

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
Date DEC 22, 1994

LIBER

3 PAGE 192

Marvin E. Myers  
Marvin E. Myers, P.S.

CRAWFORD COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO ACT 345, PA 1990

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

10 FEB 95 8:39 A.M.

ELIZABETH H. WIELAND  
REGISTER OF DEEDS

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>2W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner set by James Mullet  
1839. No record fd. Resurveyed 1858  
by Walter Warner D.S. set qr. Sec. Post.  
1. Tamarack 7 S35°N, 8 lks.  
2. Tamarack 7 N57°W, 28 lks.

Set 1/2" Bar & Cap by single proportionate meas.  
between M-1 and M-3. No cor. evidence found.  
Set Witnesses (see Sec. C)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner evidence found, set 1/2" Ir. & Cap by single proportionate measure on line between M-1 and M-3.

G.L.O. dist. to M-1 2620.2' Meas. 2625.60'.  
G.L.O. dist. to M-3 2640.0' Meas. 2645.44'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Crawford Co. Mon. Set at exact location of 1/2" Ir.  
1. Set Spk. 16" Poplar N84°E, 89.26'.  
2. Set Spk. P.P. S53°E, 77.30'.  
3. Set Spk. 14" Poplar S57°W, 34.72'.  
4. Set Spk. 14" Pine N52°W, 50.72'.

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Wayne E. Boss  
Wayne E. Boss, PS  
Surveyor's Michigan License No. 20703

Date January, 1995 No. 20703

