

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
Date Dec 29, 1994
Marvin E. Myers
Marvin E. Myers, P.S.

LIBER 3 PAGE 194

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>2W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

10 FEB 95 8:39 A.M.

ELIZABETH H. WIELAND
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Cor. originally set by James Mullet in 1839 5/8" Bar. Origin Unknown
No record fd. Resurveyed in 1858 by Walter Warner (See Wit. Fd. - Section B).
D.S. Set quarter Section Post.
1. S. Pine 6" S40°W, 30 links.
2. S. Pine 8" N41°W, 40 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Bar. Origin Unknown.

- 1. Fd. Spk. 3" J. Pine N86°E 22.01'.
- 2. Fd. Spk. 3" J. Pine S62°W, 20.84'.
- 3. Fd. Spk. 3" J. Pine N65°W, 4.00'.
- G.L.O. Warner 1858 dist. to M-3 2640' Meas. 2589.22'.
- G.L.O. Warner 1858 dist. to M-5 2640' Meas. 2609.07'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 Crawford Co. Mon. Set at exact location of 5/8" Bar.
- 1. Spk. 3" J. Pine N86° E, 22.01'.
- 2. Spk. 3" J. Pine S62°W, 20.84'.
- 3. Spk. 3" J. Pine N65° W, 4.00'.
- 4. Set Spk. 3" J. Pine N29°E, 6.86'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss
Surveyor's Michigan License No. 20703

Date January 1995

