

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

CRAWFORD COUNTY
 PEER GROUP APPROVAL
 Date Dec 29, 1994
Marvin E. Myers
 Marvin E. Myers, P.S.

LIBER 3 PAGE 195

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO ACT 345, PA 1990

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED

10 FEB 95 8:40 A.M.

ELIZABETH H. WIELAND
 REGISTER OF DEEDS

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>2W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James Mullet 1839
 Set Post cor. Sec. 12 & 13.
 1. S. Pine 8" S80°W, 45 lks.
 2. S. Pine 6" N15°W, 26 lks.
 Witnessed by Walter Warner
 in 1858.

Set cor. Sec. 12 & 13
 Probably a R.R. Iron by
 again probably A.E. Newman
 sometime around 1900.

Set cor. by R. Ostling from Newman's B.T.'s
 according to Norm Parker in his corner recital
 as recorded survey L.254 pg. 69. Parker
 says Cons. cor. is 3' East. Cor. is in Trail.
 B.T. 18" Oak N42°W, 49.4'.
 B.T. 8" S. Pine N53°E, 47.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" Bar & Cap #16939 N. Parker on centerline two-track.

1. Fd. Spk. in 14" Pine Stump N48°E, 47.81'.
 2. Fd. Spk. in 18" Oak N45°W, 50.45'.
 3. Fd. Cons. Mon. East 3.03'.
- G.L.O. to M-6 2640' Meas. 2536.08' (N. Parker).
 G.L.O. to M-4 2640' Meas. 2609.07'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 Set Crawford Co. Mon. at exact location of 1/2" Bar.
1. Spk. in 14" Pine Stump N48°E, 47.81'.
 2. Spk. in 18" Oak N45°W, 50.45'.
 3. Cons. Mon. East 3.03'.
 4. Set Spk. 18" Oak N85°E, 84.14'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by *Wayne E. Boss*
 Wayne E. Boss, PS
 Surveyor's Michigan License No. 20703

Date January 13, 1995 No. 20703

