

APR 27 1995

COMMISSION

CRAWFORD COUNTY PEER GROUP APPROVAL Date Dec 22, 1994 Marvin E. Myers Marvin E. Myers, P.S.

LIBER 3 PAGE 197

CRAWFORD COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 ALSO ACT 345, PA 1990

STATE OF MICHIGAN CRAWFORD COUNTY RECORDED

10 FEB 95 8:40 A.M.

ELIZABETH H. WIELAND REGISTER OF DEEDS

For corners in

Table with columns: CRAWFORD (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Wayne E. Ross, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numerical data points for survey locations.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James Mullet 1839 Set Post cor. Sections 13 & 24 1. Pine 8" N79°W, 41 lks. 2. B. Oak 9" S71°W, 19 lks. Mullet meas. 80.0' chains from M-9 W. Warner D.S. Measured 83.25' chains in 1858. 3/4" Iron Pipe Set. Unknown origin N. Parker used in 1973 survey and subsequent surveys. L 130, pg. 537. L 319, pg. 361. Unrecorded Parker Wit. Fd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" Pipe.

- 1. Fd. tag #16939 on P.P. S49°W, 18.62'.
2. Fd. 3/4" Pipe West 29.98'.
G.L.O. Dist. to M-6 Mullet 1839 - 2640 Meas. 2596.80' (N. Parker).
G.L.O. Dist. to M-8 Mullet 1839 - 2640 Warner 1858 - 2871 Meas. 2852.30' (N. Parker)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Crawford Co. Mon. Set at exact location of 3/4" Pipe.

- 1. Tag on P.P. S49°W, 18.62'.
2. 3/4" Pipe West 29.98'
3. Spk. 20" Oak N75°E, 59.28'.
4. Spk. 18" Oak S20°E, 38.36'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss, PS Surveyor's Michigan License No. 20703

Date January 3, 1995 No. 20703 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

