

APR 27 1995

COMMISSION

CRAWFORD COUNTY PEER GROUP APPROVAL Date Dec 22, 1994 Marvin E. Myers, P.S.

LIBER 3 PAGE 199

CRAWFORD COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

ALSO ACT 345, PA 1990

STATE OF MICHIGAN CRAWFORD COUNTY RECORDED

10 FEB 95 8:40 A.M.

ELIZABETH H. WIELAND REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Table with columns: CRAWFORD (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Grid table with columns A-M and rows 2-12. Contains numbers 1-36 in a grid pattern.

I, Wayne E. Boss, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. James Mullet 1839 Set post cor. Sections 24 & 25. 1. y Pine 6" S29°W, 9 lks. 2. Pine 6" N89°W, 7 lks. Mullet Dist. from M-11 80.00'. W. Warner D.S. 1858 Dist. 79.86'. 1 1/2" Pipe set by R. Ostling. Notes not found. N. Parker recorded cor. L.2 pg. 122. 1. B.T. 4" Maple S.W. - 25.8' (S47°W, Marlatt) 2. B.T. 4" Oak N.W. - 21.6' (N20°W, Marlatt) Additional Marlatt Wit. (1994) Surveys: Parker L. 181, pg. 552. L. 184, pg. 264. L. 170, pg. 352. Marlatt L. 381, pg. 94. L. 350, pg. 470.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fd. 1 1/2" Pipe in N.S. Fence. 1. Fd. Blz. 5" Maple N85°E, 28.0'. 2. Fd. 8" Maple S47°W, 25.8'. 3. Fd. 9" Oak N20°W, 21.6'. 4. Fd. Blz. 5" Maple North 17.4'. G.L.O. Mullet 1839 - 2640 to M-8 W. Warner D.S. 1858 - 2623.5'. 2605.70' (N. Parker) Meas. 2604.62' G.L.O. Mullet 1839 - 2640 to M-10 Warner 1858 - 2628.12' Meas. 2641.73'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 Set Crawford Co. Mon. at exact location of 1 1/2" Pipe. 1. Spk. 5" Maple N85°E, 28.33'. 2. Spk. 8" Maple S42°W, 25.97'. 3. Spk. 9" Oak N28°W, 21.72'. 4. Spk. 5" Maple N05°W, 17.58'.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss, PS Surveyor's Michigan License No. 20703

Date January 3, 1995

