

APR 27 1995

COMMISSION

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

10 FEB 95 8:41 A.M.

ELIZABETH H. WIELAND
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

CRAWFORD COUNTY
PEER GROUP APPROVAL
Date Dec 22, 1994
Marvin E. Myers
Marvin E. Myers, P.S.

LIBER 3 PAGE 200

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

For corners in

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 2W	M-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James Mullet 1839 Set quarter Section Post
1. Pine 9" S57°W, 26 lks.
2. Pine 8" N61°W, 44 lks.
Mullet dist. from M-11 40 chains.
W. Warner D.S. 1858 Meas. 40.04 chains.

1/2" Bar set by E.J. Sabatini RLS according to N. Parker. Notes not found. Parker's Wit. from survey L. 180, pg. 640.
1. 6" B. Oak S46°W, 34.7'.
2. Tag In Face 8" B. Oak N45°W, 37.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" Bar by Steel Fence Post

G.L.O. Mullet 1839 - 2640 to M-9 W. Warner D.S. 1858 - 2628.12 Meas. 2641.73'
G.L.O. Mullet 1839 - 2640 to M-11 Warner 1858 - 2642.64 Meas. 2667.70' (N. Parker)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Crawford Co. Mon. at exact location of 1/2" Bar.
1. Set Spk. 8" Oak N37°E, 16.64'.
2. Set Spk. 6" Poplar S20°E, 8.94'.
3. Set Spk. 6" Poplar S70°W, 10.32'.
4. Set Spk. 6" Poplar N47°W, 5.22'.

This position not established by original government surveyors. this monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss
Surveyor's Michigan License No. 20703

Date January 3, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983