

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 28 N. R. 2 W.	G-12
2. PROPERTY CONTROLLING IN SECTION 33	T. 28 N. R. 2 W.	5; 7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 19, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-12 Set corner by proportionate measurement between section corners, taking into account the deflection prescribed by the U.S. record. Unable to locate a previous corner, Although this position is faced by an apparent NBT blaze on pine stump, but we are unable to locate record of it.
- 5 Set corner by standard survey procedure for the subdivision of sections.
- 7 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12	5	7
Set DNR Mon. & Cedar Post	Set 5/8" Rod w/RLS Cap & Cedar Post	Set 5/8" Rod w/RLS Cap & Red-Top Post
4" Oak S70°E 5.18	8" Oak N20°W 12.60	8" Oak N47°E 16.68
6" Maple S12°E 21.74	6" W. Oak S89°W 18.43	3" Maple S44°E 6.40
24" Pine Stp. (old face in stp.) N32°E 20.5		

SIGNED BY Kenneth J. Ostling DATE 7

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY