

MAR 27 1996

COMMISSION

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

8 JAN 96 12:27 P.M.

SANDRA MOORE
REGISTER OF DEEDS

3 PAGE 231

Register of Deeds Stamp & File Number

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 3W	A-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne E. Boss, in a field survey on November 1, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. James H. Mullett, April 1839
Ran town line between T28N-R3W
& T28N-R4W setting common corners.
Set post corner T28 & 29-R3 & 4W
1. Hemlock 18" S65°W 18
2. Beech 10" N45°E 53

Kenneth J. Ostling set DNR mon. in 1974. He fd. a 1/2" ir. but disregarded it. Set cor by proportionate measurement between cor. 1/2 mi. E, 1/2 mi. S, 1 mi. N & W. LCRC L.2 pg. 38. Norm Parker used cor. in 1974 survey and by James L. Schwandt in gas well survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 D.N.R. mon. fd. set by K.J.O. in 1974 by proportionate meas. LCRC L.2 Pg. 38. No direct tie to G.L.O.

- 3. Fd J.L.S. tag 6" Maple N60°E 10.30'
- 4. Fd spk 12" Maple S15°W 17.40'
- 5. Fd J.L.S. tag 10" Twin Maple N80°W 30.44'
- 6. Fd J.L.S. tag 10" Maple N15°W 23.65'

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE DEC 19, 1995

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Fd DNR mon. left in place.

- 3. Fd J.L.S. tag 6" Maple N50°E 10.30'
- 4. Fd spk 12" Maple S15°W 17.40'
- 5. Fd J.L.S. tag 10" Twin Maple N80°W 30.44'
- 6. Fd J.L.S. tag 10" Maple N15°W 23.65'

And is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by Wayne E. Boss, PS
Surveyor's Michigan License No. 20703

Date 12/21/95