

MAR 27 1996

COMMISSION

CRAWFORD COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> (County)	Located In:	Corner(s)
1. Public Land Survey	T 28N R 3W	B-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

3 PAGE 232

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

8 JAN 96 12:27 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne E. Boss, in a field survey on November 1, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

A. Description of original monument and accessories and/or subsequent restoration:  
B-1 T28N-R3W

G.L.O. James H. Mullett, 1839  
Ran town line between T28N-R3W  
& T29N-R3W setting common corners  
Set quarter Section post  
1. Beech 12" N58°W 19  
2. Birch 12" N17°E 24

Kenneth J. Ostling in his survey of Section 31,  
T29N-R3W (1974) stated that he fd. a 1/2" ir. bar  
that was established in a survey of Section 6, T28N-  
R3W. He stated he fd. it necessary to sustain cor.  
position despite distortion of Section 31. No record  
of Section 6 survey fd. No wit. given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 1/2" ir. bar fd. Unknown origin, but used by K.J.O. (DNR surveyor) in 1974 survey of Section 31, T29N-R3W. Used in subsequent unrecorded surveys.  
  
3. Fd tag in 12" Tri-Elm N20°E 5.20'  
4. Fd tag in 8" Elm S45°E 20.94'  
5. Fd spk in 8" Maple S30°W 5.90'

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 19, 1995

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Fd 1/2" ir. bar replaced with Otsego County Mon.  
  
3. Fd tag in 12" Tri-Elm N20°E 5.20'  
4. Fd tag in 8" Elm S45°E 20.94'  
5. Fd spk in 8" Maple S30°W 5.90'  
6. Set spk in 8" Twin Ironwood N65°W 22.81'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *Wayne E. Boss*  
Surveyor's Michigan License No. 20703

Date 12/21/95

