

STATE OF MICHIGAN
 LAND CORNER RECORDATION CERTIFICATE COUNTY OF CRAWFORD
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED FOR RECORD THIS
 20th DAY OF Dec, 1993 AT
 10:00 am/pm, IN LIBER 3
 PAGE 115.

E. J. Wiland
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 3W	F-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Wayne E. Boss, in a field survey on October 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Walter Warner
 July, 1857. Reestablished
 Old 1/4 section corner
 1. Sugar 12 S45W 45 links
 2. Birch 24 N7W 38 links

1/2" Iron bar set by unknown
 Corner recorded by Norman
 Parker, July 19, 1977

Set Crawford County
 monument, replacing
 1/2" iron bar found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" Iron bar found set by unknown and replaced with a Crawford County Monument.
 The distances from F-9 to both E-9 and G-9 measure longer than G.L.O. but are similarly proportionately longer. The present location has been used in subsequent surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Found 1/2" iron bar and replaced with Crawford County monument at corner location as recorded in Liber 2, Page 142, Crawford County Records, Crawford County, Michigan. This monument is accepted as the best available evidence of the position of the corner:

- | | | |
|---------------------------|-------------|--------|
| 1. 1/2" x 18" bar | S01°28'47"E | 33' |
| 2. Spike in fence post | S15°W | 38.51' |
| 3. Spike in mail box post | S75°W | 69.01' |
| 4. Spike in P.P. | N05°W | 32.05' |

Signed by *Wayne E. Boss* Date December 13, 1993

Surveyor's Michigan License No. 20703