

CRAWFORD COUNTY  
 PEER GROUP APPROVAL  
 Date Dec 22, 1994  
Marvin E. Myers  
 Marvin E. Myers, P.S.

LIBER 3 PAGE 210

SURVEY &  
 REMONUMENTATION

APR 27 1995

CRAWFORD COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ALSO ACT 345, PA 1990

CRAWFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>3W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 CRAWFORD COUNTY  
 RECORDED

10 FEB 95 8:42 A.M.

ELIZABETH H. WIELAND  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne E. Boss, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |   |  |   |
|---|--|---|
| <p>GLO Walter Warner, 1857<br/>         Reestablish old corner<br/>         of Sections 27, 28, 33 &amp; 34<br/>         1. Birch 18, S50W, 8 links<br/>         2. Birch 16, N17E, 25 links<br/>         No notes found on original cor. placement</p> | <p>3/4" Bolt Set, Unknown Origin<br/>         A.E. Newman used G-11 in old survey but did not say what the cor. was or if he replaced cor. Used &amp; wit. by N. Parker<br/>         Cor. Cert. L. 2, pg 149<br/>         1. 37" Poplar, S45°E, 70.04'<br/>         2. 12" Tw. Maple, S60°W, 82.66'<br/>         3. Iron pin in mon. N50°E, 47.88'</p> | <p>1/2" Iron Set in Mon. Box by Marvin Myers, 1991<br/>         LLRC L. 3, pg 22<br/>         2± South of <del>E.</del> E-W Road.<br/>         1. Face of Concrete Project Marker Post N50°E, 46.95'<br/>         2. Found nail &amp; tag in NE face 48" Cottonwood, S44°E, 70.04'<br/>         3. Conc. Mon. N50°E, 47.88'<br/>         4. Nail SE Face 24" Maple, S61°W, 82.65'<br/>         5. NE Cor. Stop Sign Post, N17°W, 60.29'</p> |
|---|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1/2" Ir. Fd. in Mon. Box, PS #31600  
 1. Fd. Conc. R/W Mon. (Bent) N45°E, 47.48'  
 2. Fd. MSHD Tag 40" Poplar, S47°E, 70.13'  
 3. Fd. Nail 12" Tw. Maple, S55°W, 82.78'  
 GLO Walter Warner 1857 to F-11, 2644.62', A.E. Newman 2640', Meas. 2635.00 (N. Parker) Meas. 2637.94'  
 GLO Walter Warner 1857 to H-11, 2632.08', Meas. 2643.60' N. Parker  
 GLO Walter Warner 1857 to G-11, 2698.08', 2709.75' N. Parker, 2711.30' G. Ostling, Meas. 2710.37'  
 GLO Walter Warner 1857 to G-12, 2646.60', Meas 2659.89'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11 Crawford County Monument Set in exact location of 1/2" bar.  
 1. Conc. R/W Mon (Bent), N45°E, 47.48'  
 2. MSHD Tag 40" Poplar, S47°E, 70.13'  
 3. Nail 12" Tw. Maple, S55°W, 82.78'  
 4. E. Post of Stop Sign, N24°W, 58.71'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Wayne E. Boss  
 Surveyor's Michigan License No. 20703

Date January 3, 1995

