

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **MAR 29 2000**

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

28 DEC 99 3:03 P.M.

SABRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

CRAWFORD	Located In:	Corner Code =#
(Cont'd) SECTION		
1. Public Land Survey	T <u>28N</u> R <u>3W</u>	<u>I - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 76

I, Marvin E. Myers, in a field survey on April 9, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

James H. Mullet, D.S. G.L.O. 1839 Mon.-Post Wit: 24" White Pine S30°E 31 links 9" Sugar Maple N78°W 36 links	Norman F. Parker R.L.S.#16939 Unrecorded survey of Section 26 Mon: 1 3/4" Pipe Wit: fence corner 33' West	Norman F. Parker R.L.S.#16939 Liber 179, page 38 Mon: 3/4" Pipe in the road Wit: P.Pole N80°W 35.4' 1/2" bar N89°52'22"W 33.01'
		Norman F. Parker R.L.S.#16939 Unrecorded survey in Section 26 Mon: 1 1/2" Pipe in road Wit: None provided

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" bolt raising very old 1 1/2" well point in centerline of White Road North & South. Found 1/2" bar & cap #16939 in old fence corner West 33'. Found spike in SW face of a 14" Maple S64°E 42.05'. Accepted pipe as the best available evidence of the position of the original corner. Replaced pipe with Standard Crawford County Monument.

**CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Corner
Wit: Found spike in SW face of a 14" Maple S64°E 42.05'
Found 1/2" bar & cap #16939 West 33.0'
Set spike in 6" White Pine N81°E 39.17'
Set spike in 16" Maple N40°W 88.83'
Set Carsonite Post East 33'±



Signed by *Marvin E. Myers* Date *Sept 29, 1999*
Surveyor's Michigan License No. 31600