

**SURVEY & REMONUMENTATION**

**APR 07 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

For corners in

Crawford  
(County)

Located In:

Corner Code #

1. Public Land Survey

T28N R3W

I-11 ✓

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

5 JAN 98 10:35 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

LIBER

3 PAGE 30

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, James L. Schwandt, in a field survey on 10-13, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11 T28N-R3W  
G.L.O. J. H. Mullet, D.S.  
Fnd. Post  
7" Beech N80°W, 5 Links  
10" Beech S58°E, 56 Links

G.D. Henning #2240, 1973  
Fnd. Pavement Box in Crossroads  
10" Maple S42°W, 95.0'  
8" W. Pine S60°E, 59.0'

L. 3, P.82 LCRC B.M. Jones #23514  
Fnd. 1" Iron Bar  
36" Maple S55°W, 99.25'  
Pwr. Pole N29°W, 54.91'  
20" W. Pine S26°E, 67.53'  
Pwr. Pole S75°W, 112.8'

L.2, P. 124 LCRC, N.F. Parker #16939  
Pavement Box @ Corner  
10" Maple S42°W, 95.0'  
8" W. Pine S60°E, 59.0'

A.E. Newman, 1890  
Fnd. Sunk Sand Stone Marked 'X'  
3" Sugar N7°W, 1.46'

L.3 Pg. 26 LCRC, M.E. Myers #31600  
1/2" Bar in MDOT Pavement Box  
Fnd. Nail NW Face 29" Maple S47°W, 95.0(R) 99.3'  
Fd. Nail SW Face 18" W. Pine S23°E, 67.57'  
Fnd. Nail South Face Utility Pole S77°W, 113.02'  
US Army War Dept. Corp. Of Engineers S70°W, 109.1  
Fnd. Nail MDOT Tag NE Face 16" W. Pine  
Blaze in Face S27°E, 59.7' to Blaze

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Fnd. 1/2" Bar in Mon. Box  
Fnd. Nail West side 20" W. Pine S25°E, 67.58'  
Fnd. Nail and Tag East side 36" Maple S50°W, 98.80'  
Fnd. Stump 12" W. Pine S60°E, ±59'  
Fnd. Army Corps. of Engineers S70°W, 108.9'  
Fnd. Utility Pole No Nail S77°W, 113.80'

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE OCT 16, 1997**

*Marvin E. Myers*

**Marvin E. Myers, P.S.  
County Surveyor**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Fnd. 1/2" Bar in Mon. Box  
1/2" Bar is accepted as a careful and faithful perpetuation of the position of the original corner.

Fnd. Nail West side 20" W. Pine S25°E, 67.58'  
Fnd. Tag East side 36", Maple S50°W, 98.80'  
Fnd. Army Corps. Of Engineers Mon. S70°W, 108.90'  
Set Spk. East side PP N40°W, 47.45'



Signed by James L. Schwandt  
Surveyor's Michigan License No. \_\_\_\_\_  
26466

Date 12-15-97