

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
CRAWFORD (County)

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

28 DEC 99 3:02 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey T 28N R 3W J - 9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

LIBER 4 PAGE 75

I, Marvin E. Myers, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

James H. Mullet, D.S.
G.L.O. 1839
Mon.- Post
Wit: 15" Hemlock N21°30'E 21 links
7" Beech S40°E 21 links

Norman F. Parker R.L.S.#16939
No date given 1960-80's
Mon.-position computed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monument was located to determine a position for this corner. A previous survey of Section 26 shows a computed location for this corner midway and on line. This is the only evidence of record. The corner was placed midway and on line between the Northeast and Northwest corners. This location falls on a occupation line West and South. Two possible stump holes were located fitting the G.L.O. witnesses however no definite identification could be made due to logging in the area. This location was accepted as a careful and faithful establishment of the position of the corner. Placed a Standard Crawford County Corner.

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999

Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Corner
Wit: Set spike in SE face 2" Beech S26°W 14.84'
Set spike in E. face 4" Beech S21°E 29.32'
Set spike in S. face 4" Maple N89°E 14.17'
Set spike in E. face 6" Maple N10°E 12.79'
Set Carsonite Post North 2'±



Signed by [Signature]
Surveyor's Michigan License No. 31600

Date Dec 22, 1999