

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

28 DEC 99 3:02 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CRAWFORD (County)	Located In:	Corner Code =#
1. Public Land Survey	T 28N R 3W	K - 9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 4 PAGE 73

I, Marvin E. Myers, in a field survey on April 9, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

James H. Mullet, D.S. G.L.O. 1839 Mon.-Post Wit: 10" Hemlock S62°W 20 links 14" Hemlock N57°E 22 links	Norman F. Parker R.L.S. #16939 Unrecorded survey of Section 26 1960-80's Mon. Set 1/2"x18" iron bar in road Wit: 8" Maple N18°W 39.9' 6" Maple N71°E 20.1' 6" Ash N32°E 43.5'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" bar of record 4' West of the existing North-South centerline. Confirmed position by comparison to Parker's chainage from South and West. None of the listed accessories were located due to road construction in the area. Accepted bar as the best available evidence of the position of the original corner. Replaced 1/2" bar with Standard Crawford County Monument.

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE Sept 10, 1999

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Corner 0.3' below road surface
Wit: Set spike in S. face of a blazed 10" twin Maple N87°W 54.20'
Set spike in NW face of a 12" Maple S55°W 116.02'
Set spike in W. face of a 8" Maple N27°E 118.40'
Set spike in SE face of a 4" Maple S34°W 80.00'
Set Carsonite Post East 50.5'



Signed by *Marvin E. Myers*

Date Dec 9, 1999

Surveyor's Michigan License No. 31600