

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CRAWFORD
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 28N R 3W K - 10
 T R _____
 T R _____
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

28 DEC 99 3:02 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LIBER 4 PAGE 74

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

James H. Mullet, D.S. G.L.O. 1839 Mon.-Post Wit: 14" Beech S81°W 37 links 12" Beech N20°E 46 links	Norman F. Parker R.L.S. #16939 L.C.R.C. Liber 2, page 124 Mon. Found angle iron set by Henning R.L.S. from old witnesses Wit: Aluminum tag in 16" Maple S39°E 5.0' (Henning) Aluminum tag in 12" Cedar N64°E 47.8'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner falls in an old dump site with ±3' of junk fill. Found 16" Maple S39°E 5.0' with blaze and aluminum (Henning) tag. Found 12" Cedar N64°E 47.8' with aluminum (Henning) tag. Could not locate the angle iron itself due to a buried c. Established the location for the corner using witnesses of record and accepted as the best available evidence of the position of the original corner. Placed a Standard Crawford County Corner.

**CRAWFORD COUNTY
PEER GROUP APPROVAL**

DATE Sept 10, 1999

Marvin E. Myers

**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Crawford County Monument
Wit: Set spike in W. face 6" Ash S32°W 31.20'
 Set spike in SW face 18" Maple S39°E 5.65'
 Set spike in E. face 14" Cedar N39°E 58.54'
 Set spike in S. face 4" Yellow Birch N34°E 11.90'
 Set Carsonite Post East 1"±



Signed by *Marvin E. Myers*

Date Dec 9, 1999

Surveyor's Michigan License No. 31600