

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

CRAWFORD COUNTY


T 28 N R 3 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 - 10

CORNER MONUMENT Set Department Monument below road surface

DATE MONUMENT PLACED AND WITNESSED 6-19-70

WITNESSES TO CORNER.....



6" Cherry N 40 E 74.2'

48"x12' W. Pine Stud S 10 E 75.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement during a survey in this township. Unable to locate anything for a previous corner. The U.S. record makes this mile a straight line, although a pre 1900 road survey would appear to inject a substantial deflection at this corner, placing it South of the road. Felt bound to honor U.S. record without conclusive evidence to the contrary.

SURVEYOR'S SEAL

SIGNED *Kenneth A. Oschke* DATE 7-7-70
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68